

MSCAA project #16-1400-02-01 - Winchester Perimeter Fence Replacement – Construction

**The following is for clarifications purposes only;
there are no changes to the project manual or construction documents.**

1. Contract time clarification (see G.0.03) – Calendar Days:
The contractor will have 1 week (7 days) to mobilize at the beginning of project and 1 week (7 days) to demobilize. In addition, for fence construction:
If *only* Base Bid awarded: *62 days*
If *only* Base Bid + Add. Alt. 1 awarded: *81 days*
If *only* Base Bid + Add. Alt. 1+ Add. Alt 2 awarded: *96 days*
If Base Bid + Add. Alt. 1+ Add. Alt 2 awarded+ Add. Alt 3: *136 days*

2. Installation of the posts in concrete (see Standard Post Installation Note #1; item 4/ C.5.01)
“Contractor shall core drill concrete prior to post installation in concrete areas” –
Drawing C.5.01 notes to detail 4.

3. Removal of existing fence (see Standard Post Installation Note #3, 4/ C.5.01):
Posts shall be cut off flush to the existing grade and abandoned in place. Post holes and all disturbed areas shall be filled with non-shrink grout to match the surrounding conditions and tamped flush with the surface. The concrete erosion control strip shall be removed and disposed of off-site.